

PRE-BID NOTICE

**A NON-MANDATORY CONFERENCE**

WILL BE HELD

**3:00 PM, November 7, 2016**

IN  
ROOM 16, CITY HALL  
WINSTON-SALEM, NC

The purpose of this conference is to explain the scope of work and to explain the City of Winston-Salem's Minority and Women Business Enterprise Program as it relates to:

**Sidewalk Construction along Bethabara Road**

City of Winston-Salem staff will be available to answer any technical questions concerning this work.

**Prime bidders and subcontractors are strongly encouraged to attend this conference to understand the project and bidding requirements.**

Bids for this project are due at the time and location listed in the Advertisement.

Darren Redfield  
Purchasing Department

## RE-ADVERTISEMENT FOR BIDS

### **Sidewalk Construction along Bethabara Road** CITY OF WINSTON-SALEM

Pursuant to N.C.G.S. 143-129 and 143-128, sealed bid proposals endorsed “**Bethabara Road – FB1705**” will be received in Room 16 by the City/County Purchasing Department, 324 City Hall, 101 N. Main Street, Winston-Salem, NC until **3:00 PM, November 16, 2016**, when all bids will be publicly opened and read aloud. The City reserves the right to waive any informalities in the bidding and to reject any or all proposals.

Consideration will be given only to Contractors who submit evidence that they are properly licensed as required by Chapter 87 of the North Carolina General Statutes to perform the work.

**Compliance with the City of Winston-Salem’s Minority and Women Business Enterprise program is required on this project.** Please refer to the Special Instructions to Bidders contained in the Bidding Documents. It is MANDATORY that a completed and signed copy of the Identification of Minority Participation, and Affidavit "A", Listing of Good Faith Efforts, be completed, signed and attached to the bidder's proposal.

Plans and instructions for submitting bids may be obtained by contacting Darren Redfield at [darrenmr@cityofws.org](mailto:darrenmr@cityofws.org) (preferred), 336-747-6936, or in person at the City/County Purchasing Department, Room 324, City Hall Building, 101 North Main Street, Winston-Salem, NC 27101 during normal business hours. **Electronic plans and bidding documents are available by request.**

Two non-mandatory Pre-Bid Conferences have been previously held; however, another conference will be held to explain changes to the project. End of question period is **3:00 PM, November 9, 2016**.

All work will be in accordance with the Plans and Specifications which will be provided electronically **on or after November 1, 2016** and are available for viewing at:

- 1) City/County Purchasing Department, Room 324, City Hall Building, 101 North Main Street, Winston-Salem, NC, 336-727-2983;
- 2) Engineering Department, Room 235, Bryce A. Stuart Building, 100 East First Street, Winston-Salem, NC, 336-747-6829.

This is a formal, single prime bid. Bids shall be on a unit price basis. A Bid Guarantee shall be furnished in accordance with the Instructions to Bidders. The awarded contractor will be required to provide 100% Performance and Payment Bonds.

#### **Project Description:**

Sidewalk construction project of approximately 1,280 LF (0.274 miles) in length along Bethabara Road from Hickory Knoll Drive to Indiana Avenue. See quantity line items in the bid Proposal.

#### **Project Timeline:**

Date of Award: **December 19, 2016**

Date of Availability: **March 6, 2017**

Construction Completion: **June 2, 2017**

Liquidated Damages: **\$1,000/calendar day**

M/WBE goals: **8% M, 8% W**

## Line Item Quantities

### Bethabara Road sidewalk improvements, City Project #20519

Line Item	Sec No.	Description	Quantity	Unit
1	800	MOBILIZATION	1	LS
2	226/SP	GRADING	1	LS
3	226	UNDERCUT EXCAVATION	50	CY
4	265/SP	SELECT MATERIAL, CLASS III	30	TON
5	265/SP	SELECT MATERIAL, CLASS IV	45	TON
6	265/SP	SURGE STONE	165	TON
7	270	GEOTEXTILE FOR SOIL STABILIZATION	25	SY
8	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	150	TON
9	300/SP	FOUNDATION CONDITIONING GEOTEXTILE	400	SY
10	310	15" RC PIPE CULVERTS, CLASS III	428	LF
11	310	18" RC PIPE CULVERTS, CLASS III	418	LF
12	310	15" RC PIPE CULVERTS, CLASS IV	135	LF
13	SP	15" FLARED END SECTION	1	EA
14	340	PIPE REMOVAL	250.5	LF
15	545	INCIDENTAL STONE BASE	400	TON
16	607	MILLING ASPHALT PAVEMENT, 0" TO 2"	350	SY
17	610/SP	ASPHALT CONCRETE BASE COURSE, TYPE B25.0B	275	TON
18	610/SP	ASPHALT CONCRETE INTERM. COURSE, TYPE I19.0B	125	TON
19	610/SP	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B	150	TON
20	620/SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35	TON
21	654/SP	ASPHALT PLANT MIX, PAVEMENT REPAIR	700	TON
22	840	MASONRY DRAINAGE STRUCTURE	20	EA
23	840	MASONRY DRAINAGE STRUCTURE	4.6	LF
24	840	PIPE PLUGS	0.5	CY
25	840	FRAME WITH GRATES, STD 840.16	2	EA
26	840	FRAME WITH GRATE AND HOOD, STD 840.03, TYPE E	1	EA
27	840	FRAME WITH GRATE AND HOOD, STD 840.03, TYPE F	7	EA
28	840	FRAME WITH GRATE AND HOOD, STD 840.03, TYPE G	3	EA
29	840	FRAME WITH COVER, STD. 840.54	10	EA
30	846/SP	6" X 12" CONCRETE CURB	25	LF
31	846/SP	2'-6" CONCRETE CURB AND GUTTER	1,280	LF
32	SP	EXTEND EXISTING ROOF DRAIN	100	LF
33	848/SP	4" CONCRETE SIDEWALK	660	SY
34	848/SP	6" CONCRETE DRIVEWAY	150	SY
35	848/SP	CONCRETE CURB RAMP	6	EA
36	858/SP	ADJUSTMENT OF MANHOLES	1	EA
37	858/SP	ADJUSTMENT OF VALVE BOXES	3	EA
38	859	CONVERT EXISTING SLAB INLET TO CATCH BASIN	1	EA
39	859	CONVERT EXISTING DROP INLET TO JB WITH MH	1	EA
40	859	CONVERT EXISTING SLAB INLET TO JB WITH MH	1	EA
41	SP	RIP RAP, CLASS 'B'	15	TON
42	1105/SP	TEMPORARY TRAFFIC CONTROL	1	LS
43	1105/SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	120	SF
44	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS.)	70	LF

45	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS.)	140	LF
46	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS.)	3	LF
47	1205/SP	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS.)	2	EA
48	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (4")	170	LF
49	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (24")	1	LF
50	1205/SP	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2	EA
51	SP	6" D.I. WATER LINE	5	LF
52	SP	12" D.I. WATER LINE	90	LF
53	SP	6" GATE VALVE & BOX	1	EA
54	SP	HYDRANTS	1	EA
55	SP	HYDRANT EXTENSIONS	1	LF
56	SP	D.I. FITTINGS	3,200	LB
57	SP	RELOCATE HYDRANT	3	EA
58	SP	RELOCATE WATER CONNECTION	4	EA
59	SP	RELOCATE SEWER CONNECTION	3	EA
60	SP	MATTING FOF EROSION CONTROL	225	SY
61	SP	TEMPORARY SILT FENCE	25	LF
62	SP	COIR FIBER WATTLE	9	EA
63	SP	PIPE INLET PROTECTION	1	EA
64	SP	INLET PROTECTION	7	EA
65	SP	SEDIMENT CONTROL BAG	8	EA
66	SP	SEEDING & MULCHING (PERMANENT AND TEMPORARY)	0.50	ACR