

PRE-BID NOTICE

A NON-MANDATORY CONFERENCE

WILL BE HELD

2:00 PM, May 1, 2018

IN
ROOM 16, CITY HALL
WINSTON-SALEM, NC

The purpose of this conference is to explain the scope of work and to explain the Minority and Women Business Enterprise Subcontracting Goals as it relates to:

Sidewalk Improvements along Carver School Road

City of Winston-Salem staff will be available to answer any technical questions concerning this work.

Prime bidders and subcontractors are strongly encouraged to attend this conference to understand the project and bidding requirements.

Bids for this project are due at the time and location listed in the Advertisement.

Darren Redfield
Purchasing Department

ADVERTISEMENT FOR BIDS

Sidewalk Improvements along Carver School Road

CITY OF WINSTON-SALEM

Pursuant to N.C.G.S. 143-128 and 129, sealed bid proposals endorsed “**Carver School Rd Sidewalk Improvements – FB18265**” will be received by City/County Purchasing, 324 City Hall, 101 N. Main Street, Winston-Salem, NC in Room 16 until **2:00 PM, May 15, 2018**, when all bids will be publicly opened and read aloud. The City reserves the right to waive any informalities in the bidding and to reject any or all bid proposals.

Consideration will be given only to Contractors who submit evidence that they are properly licensed as required by Chapter 87 of the North Carolina General Statutes to perform the work.

Bidding documents and/or instructions for submitting bids may be obtained by contacting Darren Redfield at darrenmr@cityofws.org (preferred), 336-747-6936, or in person at the City/County Purchasing Department, 324 City Hall, 101 North Main Street, Winston-Salem, NC 27101 during normal business hours. All questions must be submitted in writing to receive a proper response. The End of Question period is 5:00 PM, May 8, 2018.

All work will be in accordance with the Plans and Specifications, which will be made available electronically **on or after April 30, 2018** by request, with hardcopies available for viewing at:

- 1) City/County Purchasing Department, Room 324, City Hall Building, 101 North Main Street, Winston-Salem, NC, 336-727-2983;
- 2) Engineering Department, Room 235, Bryce A. Stuart Building, 100 East First Street, Winston-Salem, NC, 336-747-6829.

This is city formal, single prime bid. Bids shall be on a unit price basis. A Bid Guarantee shall be furnished in accordance with the Instructions to Bidders. The awarded contractor will be required to provide 100% Performance and Payment Bonds.

Compliance with NCDOT’s Minority and Women Business Enterprise program is required on this project. Please refer to the Special Instructions to Bidders contained in the Bidding Documents. It is Mandatory that the LISTING OF MBE/WBE SUBCONTRACTORS form be completed and included with the bidder’s proposal.

Project Description:

Sidewalk construction along Carver School Road. Add concrete sidewalk, curb and gutter, storm drainage, narrow strip of asphalt paving.

Project Timeline Summary:

Date of Award: June 18, 2018

Date of Availability: July 16, 2018

Construction Completion: October 26, 2018

Liquidated Damages: \$1,000/calendar day

M/WBE goals: 8%M, 7%W

ITEMIZED PROPOSAL FORM

Carver School Road

City Project # 201521 (Grading, Drainage, Paving, Curb & Gutter, and Sidewalk)

<u>Line</u> <u>Item</u>	<u>NCDOT</u> <u>Section</u> <u>No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Price</u>	<u>Total</u>
1	800	MOBILIZATION	1	LS	\$	\$
2	226/SP	GRADING	1	LS	\$	\$
3	226	UNDERCUT EXCAVATION	45	CY	\$	\$
4	265/SP	SELECT MATERIAL, CLASS III	165	TON	\$	\$
5	265/SP	SELECT MATERIAL, CLASS IV	165	TON	\$	\$
6	265/SP	SURGE STONE	165	TON	\$	\$
7	270	GEOTEXTILE FOR SOIL STABILIZATION	20	SY	\$	\$
8	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	40	TON	\$	\$
9	300/SP	FOUNDATION CONDITIONING GEOTEXTILE	110	SY	\$	\$
10	310	15" RC PIPE CULVERTS, CLASS III	248	LF	\$	\$
11	340	PIPE REMOVAL	63.0	LF	\$	\$
12	520	AGGREGATE BASE COURSE	490	TON	\$	\$
13	545	INCIDENTAL STONE BASE	725	TON	\$	\$
14	607	MILLING ASPHALT PAVEMENT, 0" TO 2"	260	SY	\$	\$
15	610/SP	ASPHALT CONCRETE INTERM. COURSE, TYPE 119.0C	95	TON	\$	\$
16	610/SP	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B	80	TON	\$	\$
17	620/SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	15	TON	\$	\$
18	840	MASONRY DRAINAGE STRUCTURE	3	EA	\$	\$
19	840	FRAME WITH GRATE AND HOOD, STD 840.03, TYPE G	2	EA	\$	\$
20	840	FRAME WITH GRATE, STD 840.16	1	EA	\$	\$
21	840	FRAME WITH COVER, STD. 840.54	2	EA	\$	\$
22	SP	EXTEND EXISTING ROOF DRAIN	100	LF	\$	\$
23	SP	SIDEWALK FLUME	20	LF	\$	\$
24	846/SP	2'-6" CONCRETE CURB AND GUTTER	920	LF	\$	\$
25	848/SP	4" CONCRETE SIDEWALK	350	SY	\$	\$
26	848/SP	6" CONCRETE SIDEWALK	50	SY	\$	\$
27	848/SP	6" CONCRETE DRIVEWAY	280	SY	\$	\$
28	848/SP	CONCRETE CURB RAMP	3	EA	\$	\$
29	858/SP	ADJUSTMENT OF MANHOLES	1	EA	\$	\$
30	858/SP	ADJUSTMENT OF VALVE BOXES	2	EA	\$	\$
31	859	CONVERT EXISTING DROP INLET TO JB WITH MH	1	EA	\$	\$
32	SP	RETROFIT CATCH BASIN	1	EA	\$	\$
33	1105/SP	TEMPORARY TRAFFIC CONTROL	1	LS	\$	\$
34	1110/SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	100	SF	\$	\$
35	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS.)	930	LF	\$	\$
36	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS.)	55	LF	\$	\$
37	1205/SP	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS.)	2	EA	\$	\$
38	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (4")	730	LF	\$	\$
39	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (24")	20	LF	\$	\$
40	1667	SPECIALIZED HAND MOWING	45	MHR	\$	\$
41	SP	3/4" WATER CONNECTION	1	EA	\$	\$
42	SP	RELOCATE WATER CONNECTION	4	EA	\$	\$
43	SP	RELOCATE SEWER CONNECTION	4	EA	\$	\$
44	1510/SP	6" WATER LINE	65	LF	\$	\$
45	1510/SP	DUCTILE IRON WATER PIPE FITTINGS	65	LB	\$	\$
46	1540/SP	ABANDON 6" UTILITY PIPE	65	LF	\$	\$
47	SP	MATTING FOR EROSION CONTROL	560	SY	\$	\$
48	SP	TEMPORARY SILT FENCE	975	LF	\$	\$
49	SP	STONE OUTLET	3	EA	\$	\$
50	SP	INLET PROTECTION	4	EA	\$	\$
51	SP	SEDIMENT CONTROL BAG	2	EA	\$	\$
52	SP	SEEDING & MULCHING (PERMANENT AND TEMPORARY)	0.50	ACR	\$	\$

Total Estimated Cost \$