

PRE-BID NOTICE

A NON-MANDATORY CONFERENCE

WILL BE HELD

2:00 PM, May 3, 2018

IN
ROOM 16, CITY HALL
WINSTON-SALEM, NC

The purpose of this conference is to explain the scope of work and to explain the Minority and Women Business Enterprise Subcontracting Goals as it relates to:

Sidewalk Improvements along Miller Street

City of Winston-Salem staff will be available to answer any technical questions concerning this work.

Prime bidders and subcontractors are strongly encouraged to attend this conference to understand the project and bidding requirements.

Bids for this project are due at the time and location listed in the Advertisement.

Darren Redfield
Purchasing Department

ADVERTISEMENT FOR BIDS

Sidewalk Improvements along Miller Street CITY OF WINSTON-SALEM

Pursuant to N.C.G.S. 143-131 and city policies, sealed bid proposals endorsed “**Miller Street Sidewalk Improvements – IF18294**” will be received by City/County Purchasing, 324 City Hall, 101 N. Main Street, Winston-Salem, NC in Room 16 until **2:00 PM, May 17, 2018**, when all bids will be publicly opened and read aloud. The City reserves the right to waive any informalities in the bidding and to reject any or all bid proposals.

Consideration will be given only to Contractors who submit evidence that they are properly licensed as required by Chapter 87 of the North Carolina General Statutes to perform the work.

Instructions for submitting bids may be obtained by contacting Darren Redfield at darrenmr@cityofws.org (preferred), 336-747-6936, or in person at the City/County Purchasing Department, 324 City Hall, 101 North Main Street, Winston-Salem, NC 27101 during normal business hours. All questions must be submitted in writing to receive a proper response. The End of Question period is 5:00 PM, May 10, 2018.

All work will be in accordance with the Plans and Specifications, which will be made available electronically **on or after April 30, 2018** by request, with hardcopies available for viewing at:

- 1) City/County Purchasing Department, Room 324, City Hall Building, 101 North Main Street, Winston-Salem, NC, 336-727-2983;
- 2) Engineering Department, Room 235, Bryce A. Stuart Building, 100 East First Street, Winston-Salem, NC, 336-747-6829.

This is a state-funded project. It is an informal, single prime bid. Bids shall be on a unit price basis. A Bid Guarantee shall be furnished in accordance with the Instructions to Bidders. The awarded contractor will be required to provide 100% Performance and Payment Bonds. **Use state forms for all bonds.**

Compliance with NCDOT’s Minority and Women Business Enterprise program is required on this project. Please refer to the Special Instructions to Bidders contained in the Bidding Documents. It is Mandatory that the LISTING OF MBE/WBE SUBCONTRACTORS form be completed and included with the bidder’s proposal.

Project Description:

Sidewalk construction along Miller Street, from West First Street to Cloverdale Avenue.

Project Timeline Summary:

Date of Award: June 18, 2018

Date of Availability: July 16, 2018

Construction Completion: October 12, 2018

Liquidated Damages: \$500/calendar day

M/WBE goals: 4% MBE, 4% WBE. (May be combined together)

ESTIMATED QUANTITY LINE ITEMS on following pages.

Itemized Proposal Form
Miller Street Sidewalk Improvements
City Project # 201607 (IF No. 18242)

<u>Line</u> <u>Item</u>	<u>NCDOT</u> <u>Section</u> <u>No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Price</u>	<u>Total</u>
1	800	MOBILIZATION	1	LS	\$	\$
2	226/SP	GRADING	1	LS	\$	\$
3	226	UNDERCUT EXCAVATION	50	CY	\$	\$
4	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	225	SY	\$	\$
5	545	INCIDENTAL STONE BASE	150	TON	\$	\$
6	607	MILLING ASPHALT PAVEMENT, 0" TO 2"	265	SY	\$	\$
7	654/SP	ASPHALT PLANT MIX, PAVEMENT REPAIR	180	TON	\$	\$
8	846/SP	8" X 12" CONCRETE CURB	110	LF	\$	\$
9	846/SP	8" X 18" CONCRETE CURB	175	LF	\$	\$
10	846/SP	2'-6" CONCRETE CURB AND GUTTER	72	LF	\$	\$
11	848/SP	4" CONCRETE SIDEWALK	985	SY	\$	\$
12	848/SP	6" CONCRETE SIDEWALK	35	SY	\$	\$
13	848/SP	6" CONCRETE DRIVEWAY	55	SY	\$	\$
14	848/SP	CONCRETE CURB RAMP	9	EA	\$	\$
15	848/SP	RETROFIT EXISTING CURB RAMP	2	EA	\$	\$
16	852/SP	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	165	SY	\$	\$
17	858	ADJUSTMENT OF MANHOLES	1	EA	\$	\$
18	858	ADJUSTMENT OF CATCH BASIN (SLAB TYPE)	2	EA	\$	\$
19	1105/SP	TEMPORARY TRAFFIC CONTROL	1	LS	\$	\$
20	1110/SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	216	SF	\$	\$
21	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS.)	330	LF	\$	\$
22	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS.)	235	LF	\$	\$
23	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS.)	280	LF	\$	\$
24	1205/SP	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS.)	220	LF	\$	\$
25	1205/SP	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS.)	3	EA	\$	\$

<u>Line</u> <u>Item</u>	<u>NCDOT</u> <u>Section</u> <u>No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Price</u>	<u>Total</u>
26	1205/SP	PAINT PAVEMENT MARKING LINES (4")	445	LF	\$	\$
27	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (4")	480	LF	\$	\$
28	1205/SP	REMOVAL OF PAVEMENT MARKING LINES (24")	55	LF	\$	\$
29	1205/SP	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	3	EA	\$	\$
30	1667	SPECIALIZED HAND MOWING	45	MHR	\$	\$
31	SP	SAFETY FENCE	120	LF	\$	\$
32	SP	RELOCATE WATER CONNECTION	1	EA	\$	\$
33	SP	ADJUST WATER CONNECTION	3	EA	\$	\$
34	SP	ADJUST SEWER CONNECTION	2	EA	\$	\$
35	SP	MATTING FOR EROSION CONTROL	500	SY	\$	\$
36	SP	TEMPORARY SILT FENCE	440	LF	\$	\$
37	SP	COIR FIBER WATTLE	1	EA	\$	\$
38	SP	STONE OUTLET	4	EA	\$	\$
39	SP	INLET PROTECTION	1	EA	\$	\$
40	SP	SEDIMENT CONTROL BAG	3	EA	\$	\$
41	SP	SEEDING & MULCHING (PERMANENT AND TEMPORARY)	20,200	SF	\$	\$

Total Estimated Cost \$